



OFFICE OF THE PRINCIPAL
BIHAR NATIONAL COLLEGE
PATNA UNIVERSITY. PATNA 800005

Website: www.bncollegepatna.com

EMERGENT NOTICE INVITING QUOTATION

Quotation No: **PL-461/25**

Date: **29/08/2025**

NAME OF WORK: ROOF TREATMENT OF BUILDING OF ZOOLOGY DEPARTMENT, B.N. COLLEGE, P.U. PATNA

Sealed quotations are invited in prescribed format for this work, along with the amount of Earnest Money Deposit, as mentioned in the Terms and Conditions of this notice. For details terms and condition, please visit the office of the undersigned on any working days from 10.30 A.M. to 5.00 P.M. or website of College.

Designation of officer inviting quotation	Principal, B.N. College, Patna
Place, Time & Date of receiving of quotation	Office of the Principal, B.N. College, Patna up to 3.00 p.m. on 16.09.2025.
Place, Time & Date of opening quotation	Office of the Principal, B.N. College, Patna at 3.30 p.m. on 16.09.2025.

PRESCRIBED FORMAT

S.N.	Code No	Description	Quantity		Unit	Rate	Amount
						(Rs.)	
1	OL71	Providing skilled labours for cleaning un wanted plants including removal of existing old and damage A.P.P. etc. grown over roof and cleaning and brooming the roof for necessary works as per direction of Engineer-in-charge.	4	Day	Day		
2	6.18. 4.A	Half brick masonry with bricks of class designation 100A in foundations and plinth in : Cement mortar 1:4 (1 cement: 4 coarse send)	35	Sqm	Sqm		
3	6.19. A	Extra for half Brick masonry in superstructure above pinth level upto floor V level	35	Sqm	Sqm		
4	13.1. 2.2	15 mm cement plaster on rough side of single or half brick wall of mix 1:4(1 cement: 4 coarse sand)	103	Sqm	Sqm		
5	12.7. 8.2.	Providing and fixing on wall face unplasticised-PVC(working pressure 4 kgf per sqm) rain water pipes conforming to IS :4985 including jointing with seal ring conforming to IS: 5382 leaving 10 mm gap for thermal expansion. 110 mm diameter	11	m	m		
6	12.79 .5.2.	Providing and fixing on wall face unplasticised -PVC molded fittings/accessories for unplasticised-PVC rain water pipes conforming to (S:4985 including jointing with seal ring conforming to IS: 5382 leaving 10 mm gap for thermal expansion- 110 mm bend	12	No	Each		
7		Providing and laying APP (Atactic Polypropylene Polymer) modified prefabricated five layer 3 mm thick water proofing membrane, black finished reinforced with non-woven polyester matt consisting of a coat of bitumen primer for bitumen membrane @ 0.40 litre/ sqm by the same membrane manufacture of density at 25°C, 0.87-0.89 kg/ litre and viscosity 70-160 cps. Over the primer coat the layer of membrane shall be laid using Butane Torch and sealing all joints etc., and preparing the surface complete. The vital physical and chemical parameters of the membrane shall be as under : Joint strength in longitudinal and transverse direction at 23°C as 650/450N/5 cm. Tear strength in longitudinal and transverse direction as 300/250N. Softening point of membrane not less than 150°C. Cold flexibility shall be upto -2°C when tested in accordance with ASTM, D - 5147. The laying of membrane shall be got done through the authorised applicator of the manufacturer of membrane.3 mm thick.	304	Sqm	Sqm		


S.N.	Code No	Description	Quantity		Unit	Rate	Amount
						(Rs.)	
8	15.7.4	Demolishing brick work including stacking of serviceable material and disposal of unserviceable material within 50 meters lead: In cement mortar	2	Cum	Cum		
9	15.3.1	Removing mortar from bricks and cleaning bricks including stacking within a lead of 50m (stacks of cleaned bricks shall be measured): From brick work in cement mortar	0.9	Cum	Cum		
10	6.1.1 4A	Brick work with bricks of class designation 100A in foundations and plinth in : Cement mortar 1:6 (1 cement: 6 coarse sand)	2	Cum	Cum		
11	6.3A	Extra for Brick work in superstructure above plinth level upto floor V cum	2	Cum	Cum		
12	2602	Less, the cost of old bricks likely to be obtained and to be re used in new brick work, as per direction of Engineer-in-charge.	400	No	%0N o		
13	15.28.1	Dismantling roofing including ridges, hips valleys and gutters etc. and stacking the material within 50 metres lead of:G.S. Sheet	31	Sqm	Sqm		
14	10.1	Structural steel work in singal section fixed without connecting plate including cutting .hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	40	Kg	Kg		
15	12.6.5X.2.	Providing & fixing at all heights, levels and locations colour finish Aluminium alloy roofing sheets of alloy IS designation 31500, temper Hx8 conforming to IS 737 and dimensions as per IS code 2676 with characteristics of good formability and corrosion resistance. The profile sheets shall be fixed to truss members inslope or required pitch or curvature with Hex capheaded self drilling /tapping Stainless steel screws M6, 60mm long with 3 mm EPDM sealwasher etc. all inclusive of labour, scaffolding, T&P and sundries etc. complete as per directions of the Engineer-In Charge. {Cost of truss/frame work shall be paid separately).					
		0.71 mm, Aluminium Color coated troughed profile with center to center pitch of 200 mm, depth of 32 mm, overall profile width 1092 mm, cover width 1000mm.	31	Sqm	Sqm		
16	13.8.1.	Applying priming coat: With ready mixed zinc chromate yellow primer of approved brand and manufacture on steel galvanized iron/steel works	20	Sqm	Sqm		
17		Painting with synthetic enamel paint of approved brand and manufacture to give an even shade: Two or more coats on new work	20	Sqm	Sqm		
18		Carriage of materials:					
a		Designation 100 A bricks from 8 Km distance from site with an additional lead of 1 Km kutcha road.	2200	No	No		
b		Sone sand from Koelwar, 45 Km distance of surface road from site.	4	Cum	Cum		


S.N.	Code No	Description	Quantity		Unit	Rate	Amount
						(Rs.)	
19		Price difference of materials for Patna urban area, as prescribed in the Schedule of Rates.					
a		Designation 100 A bricks					
b		Cement	2200	No	%ON		
20		Reserved price for any other unseen work.	28	Bag	Bag		
		TOTAL AMOUNT	1	L.S.	L.S.		

Terms and conditions:

- 1 Earnest Money Deposit in the form of Bank Draft in the favour of Principal, B.N College, Patna or N.S.C./ Time Deposit of Post Office, duly pledged in the name of Principal, B.N. College, Patna @ 2% i.e.Rs.5,400/- is essentially required with quotations. Remaining amount of Security Deposits @ 8% of bill amount will be deducted from bill.
- 2 Work must be completed within 1 month after receiving work order.
- 3 Any registered agency of Government of Bihar / C.P.W.D. /M.E.S. will be considered.
- 4 Any working agency of Works Department, Patna University, Patna will also be considered for the works of Rs. 1,00,000 and under.
- 5 Payment will be considered after satisfactory completion of work and after submitting satisfactory work completion certificate.
- 6 The undersigned reserve the right to accept or reject any or all the quotations without assigning any reason.
- 7 All disputes, what so ever shall be referred to the sole arbitration of the Principal, B.N. College, Patna and his decision shall be final and binding on the agency.


 28/05/25
 PRINCIPAL
 B.N.COLLEGE, PATNA


 30/5/25


 28/05/25