



OFFICE OF THE PRINCIPAL
BIHAR NATIONAL COLLEGE
PATNA UNIVERSITY. PATNA 800005

Website: www.bncollegepatna.com

EMERGENT NOTICE INVITING QUOTATION

Quotation No: PL-464/25

Date: 29/08/2025

**NAME OF WORK: ROOF TREATMENT OF BUILDING OF B.C.A, GEOGRAPHY DEPARTMENT,
B.N.COLLEGE, P.U. PATNA**

Sealed quotations are invited in prescribed format for this work, along with the amount of Earnest Money Deposit, as mentioned in the Terms and Conditions of this notice. For details terms and condition, please visit the office of the undersigned on any working days from 10.30 A.M. to 5.00 P.M. or website of College.

Designation of officer inviting quotation	Principal, B.N. College, Patna
Place, Time & Date of receiving of quotation	Office of the Principal, B.N. College, Patna up to 3.00 p.m. on 16.09.2025
Place, Time & Date of opening quotation.	Office of the Principal, B.N. College, Patna at 3.30 p.m. on 16.09.2025.

PRESCRIBED FORMAT

S.N.	Code No	Description	Quantity	Unit	Rate	Amount (Rs.)
1	OL71	Providing skilled labours for cleaning un wanted plants including removal of existing old and damage A.P.P. etc. grown over roof and cleaning and brooming the roof for necessary works as per direction of Engineer-in-charge	10	Lab/D ay	Lab/ Day	
2	P.M.R.	Providing skilled labours, Manila rope, including cutting machines etc. For trimming branches of various Peepal trees grown around the building, as per direction of Engineer-in-charge.	1	L.S.	L.S.	
3	4.2.2	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, post. struts, buttresses, string or lacing courses, parapets, coping, bedblocks, anchor blocks, plin window sills, fillets etc. upt floor five level excluding the cost of centring, shuttering and finishing: 1:1.5:3(1 Cement: 1:5 coarse sand : 3 graded stone aggregate 20 mm nominal size)	3	Cum	Cum	

P.K.A.

6

S.N.	Code No	Description	Quantity	Unit	Rate	Amount (Rs.)
4	6.18.4 A	Half brick masonry with bricks of class designation 100A in foundations and plinth in : Cement mortar 1:4 (1 cement: 4 coarse send)	8	Sqm	Sqm	
5	13.12.1	15 mm cement plaster on rough side of single or half brick wall of mix 1:3 (1 cement :3 coarse	154	Sqm	Sqm	
6	22.20.1	Providing and laying APP (Atactic Polypropylene Polymer) modified prefabricated five layer 3 mm thick water proofing membrane, black finished reinforced with non-woven polyester matt consisting of a coat of bitumen primer for bitumen membrane @ 0.40 litre/ sqm by the same membrane manufacture of density at 25°C, 0.87-0.89 kg/ litre and viscosity 70-160 cps. Over the primer coat the layer of membrane shall be laid using Butane Torch and sealing all joints etc., and preparing the surface complete. The vital physical and chemical parameters of the membrane shall be as under : Joint strength in longitudinal and transverse direction at 23°C as 650/450N/5 cm. Tear strength in longitudinal and transverse direction as 300/250N. Softening point of membrane not less than 150°C. Cold flexibility shall be upto -2°C when tested in accordance with ASTM, D - 5147. The laying of membrane shall be got done through the authorised applicator of the manufacturer of membrane.3 mm thick.	853	Sqm	Sqm	
7	12.78.2	Providing and fixing on wall face unplasticised-PVC(working pressure 4 kgf per sqm) rain water pipes conforming to IS :4985 including jointing with seal ring conforming to IS: 5382 leaving 10 mm gap for thermal expansion. 110 mm diameter	15	m	m	
8	12.79.5.2	Providing and fixing on wall face unplasticised - PVC molded fittings/accessories for unplasticised-PVC rain water pipes conforming to (S:4985 including jointing with seal ring conforming to IS: 5382 leaving 10 mm gap for thermal expansion.110 mm bend	5	No	Each	

P. K. Arora


5

S.N.	Code No	Description	Quantity	Unit	Rate (Rs.)	Amount
9	S.O.R.	Carriage of materials:				
a		Sone sand from Koelwar, 45 Km distance of surface road.	5	Cum	Cum	
b		Stone aggregate from Manpur, Gaya, 100 Km distance of surface road	3	Cum	Cum	
c		Designation 100 A bricks from 8 Km distance of surface road with an additional lead of 1 Km of	400	No	%0N o	
10	S.O.R.	Price difference of materials for Patna urban area:				
a		Cement.	55	Bag	Bag	
b		Designation 100 A bricks .	400	No	%0N ~	
11		Reserved amount for any other un seen work.	1	Job	L.S.	
TOTAL AMOUNT						

Terms and conditions:

- 1 Earnest Money Deposit in the form of Bank Draft in the favour of Principal, B.N College, Patna or N.S.C./ Time Deposit of Post Office , duly pledged in the name of Principal, B.N. College, Patna @ 2% i.e.Rs.9.900/- is essentially required with quotations. Remaining amount of Security Deposits @ 8% of bill amount will be deducted from bill.
- 2 Work must be completed within 1 month after receiving work order.
- 3 Any registered agency of Government of Bihar / C.P.W.D. /M.E.S. will be considered.
- 4 Any working agency of Works Department, Patna University, Patna will also be considered for the works of Rs. 1,00,000 and under.
- 5 Payment will be considered after satisfactory completion of work and after submitting satisfactory work completion certificate.
- 6 The undersigned reserve the right to accept or reject any or all the quotations without assigning any reason.
- 7 All disputes, what so ever shall be referred to the sole arbitration of the Principal, B.N. College, Patna and his decision shall be final and binding on the agency.


 30/08/25
 PRINCIPAL
 B.N.COLLEGE, PATNA


 30/8/25

P.K.A.K
 28/08/25