



OFFICE OF THE PRINCIPAL
BIHAR NATIONAL COLLEGE
PATNA UNIVERSITY. PATNA 800005

Website: www.bncollegapatna.com

EMERGENT NOTICE INVITING QUOTATION

Quotation No:

Date:

**NAME OF WORK: CONSTRUCTION OF A PORTION OF BOUNDARY WALL AT SOUTH- EAST CORNER
& RAISING OF A PORTION OF BOUNDARY WALL AT EASTERN SIDE IN THE CAMPUS OF B.N.
COLLEGE, P.U. PATNA**

Sealed quotations are invited in prescribed format for this work, along with the amount of Earnest Money Deposit, as mentioned in the Terms and Conditions of this notice. For details terms and condition , please visit the office of the undersigned on any working days from 10.30 A.M. to 5.00 P.M. or website of College.

Designation of officer inviting quotation	Principal, B.N. College, Patna
Place, Time & Date of receiving of quotation	Office of the Principal, B.N. College, Patna up to 3.00 p.m. on 24.09.2025.
Place, Time & Date of opening quotation	Office of the Principal, B.N. College, Patna at 3.30 p.m. on 24.09.2025.

PRESCRIBED FORMAT

S.N.	Code No	Description	Quantity		Unit	Rate	Amount
						(Rs.)	
1	15.36.	Dismantling barbed wire or flexible rope in fencing including making roll; and stacking within 50 metres lead.	44	Kg	Kg		
2	15.7.4	Demolishing brick work including stacking of serviceable material and disposal of unserviceable material within 50 meters lead: In cement mortar	3.5	Cum	Cum		
3	15.3.1	Removing mortar from bricks and cleaning bricks including stacking within a lead of 50m (stacks of cleaned bricks shall be measured): From brick work in cement mortar	1.7	Cum	Cum		
4	2602A	Less, the cost of old bricks likely to be obtained from dismantling of pillar heads of boundary walls, as per direction of Engineer-in-charge.	691	No	%0No		
5		Centring and shuttering including strutting, propping etc. and removal of form					
a	5.9.5	for Lintels, beams, plinth bams, griders, bressumers and contilevers	18	Sqm	Sqm		
b	5.9.1	Foundations, footings, bases of columns etc. for mass concrete	10	Sqm	Sqm		
c	5.9.6	Columns, Pillars, Piers, Abutments, Posts and Struts	14	Sqm	Sqm		
6	5.3.	Reinforced cement concrete work in beams, suspended floors, roofs having slope upto 15, landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases upto floor five level excluding the cost of centring, shuttering, finishing and reinforcement with 1:2:4 (1 cement:2 coarse sand:4 graded stone aggregate 20 mm nominal size).	3	Cum	Cum		

P. K. Singh
28/9/25

Code No	Description	Quantity		Unit	Rate	Amount		
					(Rs.)			
7	5.33B.4	Add or deduct for providing richer or leaner mixes respectively at all floor levels- Providing M-15grade R.C.C instead of M-20 grade R.C.C.		3	Cum	Cum		
8	20.3A.1	Making 25 cm (10") dia bore up to 4 mtr depth below ground with hand auger of approved quality in ordinary soi! (vide classification of soil item A) true to plumb and without eccentricity in any stage of operation and disposal of the excavated earth up to 50 mtr , Lead in eluding all lifts , all complete as per approved disign and direction of E/I Details of cost for 4 piles of 4 m= 16 mtrs depth)		28	m	m		
9	2.28.	Supplying and Filling in plinth with local sand and under floors including, watering, ramming consolidating and dressing complete.		1	Cum	Cum		
10	11.72.	Providing designation 100 A one brick flat soling joints filled with local sand including cost of watering, taxes, royalty all complete as per building specification and direction of E/I,		4	Sqm	Sqm		
11	5.1.2	Providing and laying in position specified grade of reinforced cement concrete excluding the cost of centring,shuttering,finishing and reinforcement-All work up to plinth level. 1:1:5:3(1 cement: 1.5 coarse sand:3 graded stone aggregate 20 mm nominal size)		3	Cum	Cum		
12	5.2.2	Reinforced cement concrete work in wall (any thickness), including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts, etc. upt floor five level excluding cost of centring, shuttering, finishin and reinforcement- 1:1:5:3(1 cement: 1.5 coarse sand:3 graded stone aggregate 20mm nominal size)		2	Cum	Cum		
13		Reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete.						
a	5.22.1	Mild steel 6.00 mm dia		37	Kg	Kg		
b	5.22.7 A	Thermo-Mechanically Treated bars TMTC-500-8mm dia.		112	Kg	Kg		
c	5.22.7 C.	Thermo-Mechanically Treated bars TMTC-500-12mm dia.		308	Kg	Kg		
14	6.1.12/1	Brick work with bricks of class designation 100A in foundations and plinth in : Cement mortar 1 :.4 (1 cement: 4 coarse sand)		21	Cum	Cum		
15	6.3A	Extra for Brick work in superstructure above plinth level upto floor V cum		21	Cum	Cum		

P.16A
08/10/25


Code No	Description	Quantity		Unit	Rate	Amount
					(Rs.)	
6 16.53.	Providing and fixing concertina coil fencing with punched tape concertina coil 600 mm dia 10 metre openable length (total length 90 m), having 50 nos rounds per 6 metre length, upto 3 m height of wall with existing angle iron 'Y' shaped placed 2.4 m or 3.00 m apart and with 9 horizontal R.B.T. reinforced barbed wire, stud tied with G.I. staples and G.I. clips to retain horizontal, including necessary bolts or G.I. barbed wire tied to angle iron, all complete as per direction of Engineer-in-charge, with reinforced barbed tape(R.B.T.) / Spring core (2.5mm thick) wire of high tensile strength of 165 kg/ sq.mm withtape (0.52 mm thick) and weight43.478 gm/ metre (cost of M.S. angle, C.C. blocks shall be paid separately)	71	m	m		
17 9.48.2	Providing and fixing M.S. grills of required pattern in frames of windowsetc. with M.S. flats, square or round bars etc. including priming coat with approved steel primer all complete. Fixed to openings/ wooden frames with rawl plugs screws etc	271	Kg	Kg		
18 13.11.2	Cement plaster in course sand, 12 mm cement plaster of mix: 1:4(1 cement :4 coarse sand)	129	Sqm	Sqm		
19 13.12.2	Cement plaster in course sand, 15 mm cement plaster on rough side of single or half brick wall of mix: 1:4(1 cement :4 coarse sand)	155	Sqm	Sqm		
20 13.46.1	Finishing walls with Acrylic Smooth exterior paint of required shade :New work (Two or more coat applied @ 1.67 ltr/ 10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/ 10 sqm)	284	Sqm	Sqm		
21 14.66.1	Finishing walls with Acrylic Smooth exterior paint of required shade: Old work (Two or more coat applied @ 1.67 ltr/ 10 sqm) on existing cement paint surface	48	Sqm	Sqm		
22 13.93.1	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade: Two or more coats on new work	14	Sqm	Sqm		
23	Carriage of materials:					
a	Designation 100 A bricks from 8 Km distance from site with an additional lead of 1 Km kutcha road.	7900	No	%0No		
b	Sone sand from Koelwar, 45 Km distance of surface road from site.	17	Cum	Cum		
c	Stone aggregate from Manpur, Gaya 100 Km distance of surface road.	7.7	Cum	Cum		
d	Local sand from 2 Km lead of surface road and 1 Km lead of Kutcha road.	2	Cum	Cum		

Code No	Description	Quantity		Unit	Rate	Amount
					(Rs.)	
4	S.O.R. Price difference of materials for Patna urban area, as prescribed in the Schedule of Rates.					
a	Designation 100 A bricks	4100	No	%0No		
b	Cement	72	Bag	Bag		
25	Reserved price for any other unseen work.	1	L.S.	L.S.		
TOTAL						

Terms and conditions:

- 1 Earnest Money Deposit in the form of Bank Draft in the favour of Principal, B.N College, Patna or N.S.C./ Time Deposit of Post Office , duly pledged in the name of Principal, B.N. College, Patna @ 2% i.e.Rs.9,100/- is essentially required with quotations. Remaining amount of Security Deposits @ 8% of bill amount will be deducted from bill.
- 2 Work must be completed within 2 months after receiving work order.
- 3 Any registered agency of Government of Bihar / C.P.W.D. /M.E.S. will be considered.
- 4 Any working agency of Works Department, Patna University, Patna will also be considered for the works of Rs. 1,00,000 and under.
- 5 Payment will be considered after satisfactory completion of work and after submitting satisfactory work completion certificate.
- 6 The undersigned reserve the right to accept or reject any or all the quotations without assigning any reason.
- 7 All disputes, what so ever shall be referred to the sole arbitration of the Principal, B.N. College, Patna and his decision shall be final and binding on the agency.


PRINCIPAL
B.N.COLLEGE, PATNA


 11/09/25