



OFFICE OF THE PRINCIPAL  
BIHAR NATIONAL COLLEGE  
PATNA UNIVERSITY. PATNA 800005

Website: www.bncollegepatna.com

**EMERGENT NOTICE INVITING QUOTATION**

Quotation No:

Date:

**NAME OF WORK: CONSTRUCTION OF A SPIRAL STAIRCASE FROM FROM FIRST FLOOR TO THE ROOF AT MAIN BUILDING, B.N. COLLEGE, P.U. PATNA**

Sealed quotations are invited in prescribed format for this work, along with the amount of Earnest Money Deposit, as mentioned in the Terms and Conditions of this notice. For details terms and condition, please visit the office of the undersigned on any working days from 10.30 A.M. to 5.00 P.M. or website of College.

Designation of officer inviting quotation	Principal, B.N. College, Patna
Place, Time & Date of receiving of quotation	Office of the Principal, B.N. College, Patna up to 3.00 p.m. on 24.09.2025.
Place, Time & Date of opening quotation	Office of the Principal, B.N. College, Patna at 3.30 p.m. on 24.09.2025.

**PRESCRIBED FORMAT**

S.N.	Code No	Description	Quantity	Unit	Rate		Amount	
							(Rs.)	
<b>PART A: CONSTRUCTION OF SPIRAL STEEL STAIRCASE</b>								
1		Providing and fixing M.S grills of required pattern in frames of windows etc. with M.S. flats, square or round bars etc. including priming coat with approved steel primer all complete.						
a	9.48.1	Fixed to steel windows by welding	400	Kg	Kg			
b	9.48.2	fixed to opening /wooden frames with rawl plugs and screws	125	Kg	Kg			
2	13.9.3.1	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade: Two or more coats on new work	50	Sqm	Sqm			
3		Reserved price of any other un seen work.	1	L.S.	L.S.			
<b>PART B: CONSTRUCTION OF STAIR HEAD ROOM</b>								
1	15.7.4	Demolishing brick work including stacking of serviceable material and disposal of unserviceable material within 50 meters lead: In cement mortar	0.4	Sqm	Sqm			
2	6.1.1.2/1	Brick work with bricks of class designation 100 A in foundations and plinth in : Cement mortar 1 :4 (1 cement: 4 coarse sand )	0.60	Cum	Cum			
3	6.3A	Extra for Brick work in super structure above plinth level up to floor V .	0.60	Cum	Cum			
4	6.18.4A	Half brick masonry with bricks of class designation 100A in foundations and plinth in :Cement mortar 1:4 (1 cement: 4 coarse send)	14	Sqm	Sqm			

0/0


S.N.	Code No	Description	Quantity		Unit	Rate	Amount
						(Rs.)	
5	6.19A	Extra for half Brick masonry in superstructure above pinth level upto floor V level.	14	Sqm	Sqm		
6	13.1 1.2	Cement plaster in course sand 12 mm cement plaster of mix: 1:4(1 cement :4 coarse sand)	23	Sqm	Sqm		
7	13.1 2.2.	15 mm cement plaster on rough side of single or half brick wall of mix 1:4(1 cement: 4 coarse sand )	16	Sqm	Sqm		
8	13.4 6.1	Finishing walls with Acrylic Smooth exterior paint of required shade :New work (Two or more coat applied @ 1.67 ltr/ 10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/ 10 sqm)	39	Sqm	Sqm		
9	5.3	Reinforced cement concrete work in beams,suspended floors, roofs having slope up to1.5, landings, balconiec,shelves,chajjas, lintels, bands, plain window sills, stair cases and spiral staircases up to floor five level excluding the cost of centring, shuttering, finishing and reinforcement with 1:2:4(1cement: 2 coarse sand: 4 graded stone aggregate 20 mm nominal size).	0.4	Cum	Cum		
10	5.9.5	Centring and shuttering including strutting, propping etc. and removal of form for.Lintels, beams, plinth bams, griders, bressumers and contilevers.	6	Sqm	Sqm		
11	5.22. 7A	Reinforcement for R.C.C.work including straightening,cutting, bending, placing in position and binding all complete. Thermo-Mechanically Treated bars TMTC-500-8mm dia.	25	Kg	Kg		
12	10.1.	Structural steel work in singal section fixed without connecting plate including cutting .hoisting, fixing in position and applying a priming coat of approved steel	25	Kg	Kg		
13	12.6 5X.2	Providing & fixing at all heights, levels and locations colour finish Aluminium alloy roofing sheets of alloy IS designation 31500, temper Hx8 conforming to IS 737 and dimensions as per IS code 2676 with characteristics of good formability and corrosion resistance. Theprofile sheets shall be fixed to truss members inslope or required pitch or curvature with Hex capheaded self drilling /tapping Stainless steel screws M6, 60mm long with 3 mm EPDM sealwasher etc. all inclusive of labour, scaffolding, T&P and sundries etc. complete as per directions of the Engineer-In Charge. {Cost of truss/frame work shall be paid separately).					
		0.71 mm, Aluminium Color coated troughed profile with center to center pitch of 200 mm, depth of 32 mm, overall profile width1092 mm, cover width 1000mm.	6	Sqm	Sqm		
14	9.48. 2.	Providing and fixing M.S. grills of required pattern in frames of windows etc. with M.S. flats, square or round bars etc. including priming coat with approved steel primer all complete.fixed to opening /wooden frames with rawl plugs and screws	40	Kg	Kg		

P.I.C.


S.N.	Code No	Description	Quantity		Unit	Rate	Amount	
15	13.8 1.3	Applying priming coat: With ready mixed zinc chromate yellow primer of approved brand and manufacture on steel galvanized iron/steel works	10	Sqm	Sqm		(Rs.)	
16	13.9 3.1	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade: Two or more coats on new work	10	Sqm	Sqm			
17		Carriage of materials for Patna urban area:						
a		Designation 100 A bricks from Fatuha 8 Km distance from site.	1000	No	%0No			
b		Stone aggregate from Manpur, Gaya 100 Km distance of surface road.	0.4	Cum	Cum			
c		Sone sand from Koelwar, 45 Km distance of road.	2	Cum	Cum			
18		Price difference for Patna urban area.						
a		Designation 100 A bricks .	1000	No	%0No			
b		Cement	13	Bag	Bag			
19		Reserved price for any other un seen work to be done as per requirement and direction of engineer in charge.	1	L.S.	L.S.			
TOTAL								

**Terms and conditions:**

- 1 Earnest Money Deposit in the form of Bank Draft in the favour of Principal, B.N College, Patna or N.S.C./ Time Deposit of Post Office , duly pledged in the name of Principal, B.N. College, Patna @ 2% i.e.Rs.3,000/- is essentially required with quotations. Remaining amount of Security Deposits @ 8% of bill amount will be deducted from bill.
- 2 Work must be completed within 2 months after receiving work order.
- 3 Any registered agency of Government of Bihar / C.P.W.D. /M.E.S. will be considered.
- 4 Any working agency of Works Department, Patna University, Patna will also be considered for the works of Rs. 1,00,000 and under.
- 5 Payment will be considered after satisfactory completion of work and after submitting satisfactory work completion certificate.
- 6 The undersigned reserve the right to accept or reject any or all the quotations without assigning any reason.
- 7 All disputes, what so ever shall be referred to the sole arbitration of the Principal, B.N. College, Patna and his decision shall be final and binding on the agency

  
 PRINCIPAL  
 B.N.COLLEGE, PATNA

  
 11/09/25

  
 P.K.A.K.  
 08/09/25