



OFFICE OF THE PRINCIPAL, B.N COLLEGE, PATNA

EMERGENT NOTICE INVITING QUOTATION

Quotation No: 02/2024-25

Date:

NAME OF THE WORK : REPAIR AND RENOVATION OF EASTERN SIDE CHAMBER OF PRINCIPAL, B.N. COLLEGE, P.U. PATNA

Designation of Officer inviting quotation	Principal, B.N. College, Patna
Place, Time & Date of receiving of quotation	Office of the Principal B.N. College, Patna up to 3:00 p.m on 10/12/2024
Place, Time & Date of opening of quotation	Office of the , Principal B.N.College, Patna up to 3:30 p.m on 10.12.2024

Sealed quotations are invited in prescribed format for this work. For details terms and condition, please visit the office of the undersigned on any working days from 10:34 A.M. to 5:00 P.M.

PRESCRIBED FORMAT

Sl.No.	Description	Quantity	Unit	Rate	Amount
PART A: REPAIR, PAINTING AND FIXING WALL PAPERS IN THE EASTERN SIDE CHAMBER					
1	Repairs to plaster of thickness 12mm to 20 mm in patches of area 2.5 sq.meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in-Charge.	10	Sqm	Sqm	
2	Providing and applying white cement based putty of average thickness 2mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	50	Sqm	Sqm	
3	Providing skilled labours for removing old and damage wall papers, photos etc and refixing photos as per direction of Engineer-in-charge plastered wall surface to prepare the surface even and smooth complete.	8	Lab/Day	Lab/Day	
4	Removing dry or oil bound distemper by scrapping, sand paper and preparing the surfaces smooth including necessary repair scratches etc. complete	9.7	Sqm	Sqm	
5	Finishing walls with Acrylic Smooth exterior paint of required shade: old work (Two or more coa applied @1.67ltr/10sqm) on existing cement paint surface	51	Sqm	Sqm	
6	Providing wall papers of approved quality, as per specification and direction of Engineer-in-charge	841	Sft	Sft	
7	Providing 18mm thick block board with commercial ply veneering on both side of approved quality for covering ventilators, as per direction of Engineer-in - charge	1.2	Sqm	Sqm	
8	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade Two or more coats on new work	33	Sqm	Sqm	
9	Cairrage of materials: Sone sand from Koelwar, 45 km distance of surface road	1	Cum	Cum	
10	Price difference of materials for Patna urban area: Ordinary Portland Cement	2	Bag	Bag	
11	Reserved price for any othe un seen work	1	L.S	L.S	3708 3708

PART B: REPAIR, PAINTING OF STORE ROOM, PANTRY AREA, WASH ROOM AND STAIR ROOM NEAR CHAMBER OF PRINCIPAL

Sl.No.	Description	Quantity		Unit	Rate	Amount
1	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq. meter sand under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in-Charge. With cement mortar 1:4 (1 cement: 4 coarse sand)	30	Sqm	Sqm		
2	Providing and applying white cement based putty of average thickness 2mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	30		Sqm		
3	Providing skilled labours for removing old and damage materials etc as per direction of Engineer-in-charge	2	Lab/Day	Lab/Day		
4	Removing dry or oil bound distemper by scrapping, sandpaper and preparing the surface smooth including necessary repairs scratches etc. complete	166	Sqm	Sqm		
5	Finishing walls with Acrylic Smooth exterior paint of required shade: Old work (Two or more coats applied @ 1.67ltr/10sqm) on existing cement paint surface	196	Sqm	Sqm		
6	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade: Two or more coats on new work	20	Sqm	Sqm		
7	Cairrage of materials: some sand from Koelwar, 45 km distance of surface road	1	Cum	Cum		
8	Price difference of materials for Patna urban area: Ordinary Portland Cement	2	Bag	Bag		
9	Reserved price for any other un seen work	1	L.S	L.S	3299	3299

PART C: PREPARATION OF A CUPBOARD IN THE PANTRY AREA


1	Providing and fixing bright /matt finished Stainless Steel handles of approved quality & make with necessary screws etc all complete. 125 mm	4	No	Each		
2	Providing and fixing cupboard shutter with 19 mm thick one side decorative and otherside balancing lamination factory pressed BWP grade marine ply as per IS 710 of approved brand including 2mm thick PVC edge banding tape with hot glue by edge bending machine etc. with auto closing spring loaded hinges (hydraulic type) etc. complete as per direction of Engineer-in-charge. (Payment of providing and fixing auto closing hinges shall be paid separately)	7	Sqm	Sqm		

S.No.	Description	Quantity		Unit	Rate	Amount
3	Providing and fixing stainless steels of closings pring hinges at 0 degree hinges(hydraulic type) of approved make/brand to cupboard shutters with full threaded steel screws including making necessary recess in board and finished etc. complete as per direction of Engineer-in-charge.	8	No			
4	Reserved price for any othe un seen work	1	L.S	L.S	3692	3692

TOTAL

Terms and Conditions

- 1 Work must be completed within a time period of 1 month.
- 2 Rate of Serial number 11 of Part A, 6 of Part B and 3 of Part C are fixed Rs.3708, Rs.3299 and Rs.3692 respectively.
- 3 Any registered agency of Government of Bihar/ C.P.W.D./ M.E.S will be cosidered.
- 4 Payment will be considered after satisfactory completion of work and after submitting satisfactory work completion certificate.
- 5 The undersigned reserve the right to accept or reject any or all the quotations without assogning any reason
- 6 All disputes, what se ever shall be referred to the sole arbitration of the Principal B.N. College and his decision shall be final and binding on the agency.


PRINCIPAL
B.N. COLLEGE, PATNA

